

NOTICE OF PUBLIC MEETING - Street Committee

The City of Adel Street Committee will meet at Adel City Hall, 301 S. 10th Street Adel, Iowa, in the Council Chambers on Tuesday, August 7, 2018 at 6:00 p.m.

AGENDA

- 1. Call to Order
- 2. Approval of Minutes July 9, 2018
- 3. Updates on Adel Growth & Safety Transportation Project Southside
 - a. HWY 169 Improvements & Turning Lanes
 - b. Trails/Sidewalks & Underpass
 - c. Meadow Road Surfacing
 - d. Any Schedule Updates? Future Public Meeting?
 - e. Consider Focus Group / Steering Committee
- 4. Review of McClure Engineering Estimates for Potential Overlay Projects (Unused 2017 Main Street Bond Proceeds)
- 5. Dallas County Parking Lot Rehabilitation Consider No Parking on North 10th Street between Court and Rapids
- 6. Any Other Business
- 7. Adjournment



July 9, 2018 Street Committee – Minutes

The City of Adel's Street Committee met at Adel City Hall, 301 S. 10th Street, Adel, Iowa, in the Council Chambers on July 9, 2018 at 6:00 p.m.

The Street Committee meeting was called to order at 6:00 p.m. by Chair Rob Christensen. Members present: Christensen and Selby. Others in attendance: Council members McAdon and Ockerman, City Administrator Brown, Public Works Director Overton, Finance Director Sandquist, McClure Engineering rep. Schug, and some residents.

Selby motioned, seconded by Christensen, to approve the May 1, 2018 minutes. Motion carried unanimously.

Discussion began on the Adel Growth & Safety Transportation Project, which includes widening HWY 169, trails, an underpass, and paving Meadow Road. Schug presented a preliminary layout. The layout showed a section of HWY 169 from Greenwood Hills Drive to 302^{nd} Place. The preliminary concept included sections with a middle turn lane, medians, and right-hand turn lanes. The sidewalks and trails, which are on both sides, are connected by an underpass.

Schug noted that the City would be meeting with the DOT on July 12 to request additional funding (i.e., the DOT is already funding \$1.5 million). The DOT has indicated that it may do an overlay project on HWY 169 from De Soto to Adel. It could be beneficial to align these projects to get a better bid price, though it may cause a delay.

Schug stated that the revised preliminary cost estimate of \$5.783 million was higher due to the medians. This estimate will likely change. Schug noted that the medians would help slow speeds down. Schug noted that two additional public information meetings would be scheduled at a later date.

Discussion moved to the DOT Corridor Access Agreements. Schug noted that these proposed agreements, which dictate access onto HWY 6 and HWY 169, are being revised by the DOT. There is no timeline, but they are expected to be issued later this year. Schug noted that the City will need to decide on the R-16 realignment at that point.

Discussion moved to the unused 2017 Main Street Bond proceeds. Brown noted that approximately \$451,000 was unused and that it can be used on practically any infrastructure project. The unused funds appear to be due to the lower bids and lower final costs. Schug noted that the City also tried to maximize the USDA-RD funds. Christensen noted that the dollar amount may allow for overlay work on phases 1-3 from the 2017 Streets CIP. Two methods are available: traditional overlay or crack and seat. Schug stated the latter costs 20% more but lasts longer. The committee will review next month.

Discussion moved to the County's parking project. Overton stated that the County would be resurfacing the driver's license parking lot with porous pavers and installing angled parking on North 10th Street. The final site plan will be delivered soon. Ockerman suggested that the County close one parking entrance. The committee will review the final plans next month.

Discussion moved to the proposal of "No Parking" near 318 South 9th (i.e., the new bed and breakfast in the old "Big Blue" house). Overton stated that this section can become crowded with traffic turning off of Greene Street. Ockerman suggested that the "No Parking" area go to the Raccoon River Valley Trail (RRVT).

Selby motioned, seconded by Christensen, to recommend to council that "No Parking" be implemented on South 9th Street from Greene Street to the RRVT. Motion carried unanimously. Brown will send a letter to property owners.

Discussion moved to the recent curb house number painting that a private company offered residents. Christensen noted that the company's flyers looked like they came from or were endorsed by the City, though they were not. Christensen asked whether the City had any liability, though it is unclear. Brown will check with other cities on this general issue.

With no other business, the meeting was adjourned at approximately 6:50 p.m.

Respectfully submitted, Anthony Brown, City Administrator


PARKING LOT REHABILITATION

PHASE 1 - DMV PARKING LOT & 10th STREET PARKING

ADEL, IOWA

AUGUST 2018





SHEET NO
TITLE


1 TITLE SHEET
2 LEGEND & SYMBOLS
3 QUANTITIES AND ESTIMATE REFERENCE NOTES
4 GENERAL NOTES
5 STAGING NOTES
6-7 REMOVAL SHEETS
8-9 PROPOSED LAYOUT SHEETS
10 TYPICAL SECTION
11 JOINTING DETAILS
12 MISCELLANEOUS DETAILS
13-14 PROPOSED GRADING SHEETS
15-18 SIDEWALK SHEETS
19-20 PAVEMENT MARKINGS



PREPARED FOR DALLAS COUNTY, IOWA

902 COURT STREET ADEL, IOWA 50003 515-993-5806

CHAIR		
1		
1		
	_	





PREPARED BY



500 SW 7TH STREET, SUITE 301 DES MOINES, IOWA 50309

T 515.323.7910 F 319.232.0271

			STANDARD SYMBOLS
$\overline{(\cdot)}$	Interstate Highway Symbol	(ST)	Septic Tank
$\stackrel{\sim}{\Box}$	U.S. Highway Symbol	©	Cistern
$\widetilde{\bullet}$	Iowa Highway Symbol	(LP)	L.P. Gas Tank (No Footing)
	County Road Highway Symbol	(UST)	Underground Storage Tank
$\overline{\triangle}$	Evergreen Tree		Latrine
<u>(</u> ,)	Deciduous Tree		Luminaire
æ.	Fruit Tree	*	Traffic Signal
£\$\$}	Shrub (Bushes)	*	Traffic Signal with Luminaire
~~~	Timber	,	Telephone Pedestal
mmn	Hedge		Television Pedestal
R	Stump	-	Telephone Pole
	Swamp	$\rightarrow$	Telephone Pole (Second Company)
≡	Rock Outcrop	-	Telephone Pole (Third Company)
0000	Broken Concrete	-	Telephone Pole (Fourth Company)
$ \begin{smallmatrix} \Delta & \Delta & \Delta & \Delta \\ \nabla & \nabla & \nabla & \nabla \end{smallmatrix} $	Revetment (Rip Rap)		Telephone Pole (Fifth Company)
+	Cemetery	$\Rightarrow$	Power Pole
G	Grave	<del></del>	Power Pole (Second Company)
(CV)	Cave	<b>—</b>	Power Pole (Third Company)
(SH)	Sink Hole		Power Pole (Fourth Company)
	Board Fence	-	Power Pole (Fifth Company)
##	Chain Link or Security Fence		Electrical Highline Tower (Metal or Concrete)
×	Wire Fence	<b>-</b>	Telephone Riser Pole
<b>△</b>	Terrace		Power Riser Pole
****	Earth Dam or Dike (Existing)	-	Telegraph Pole
****	Earth Dam or Dike (Proposed)	Q	Satellite TV Dish
——⊙	Tile Outlet	W	Existing Water Line
	Edge of Water	W2	Existing Water Line (Second Company)
<b></b> >	Existing Drainage	San	Existing Sanitary Sewer Line
<b>→</b>	Proposed Drainage	——т——	Existing Telephone Line
■	Right of Way Rail or Lot Corner	—— Т2 ——	Existing Telephone Line (Second Company)
	Concrete Monument	— го —	Existing Fiber Optics Telephone Line
X	Well	—— St. S. ——	Existing Storm Sewer Line
	Windmill	— —G— —	Existing Gas Line
$\otimes$	Beehive Intake	— — G-HP— —	Existing High Pressure Gas Line
	Existing Intake	— —G2— —	Existing Gas Line (Second Company)
	Proposed Intake	G2-HP	Existing High Pressure Gas Line (Second Company)
$oldsymbol{\Theta}$	Existing Utility Access (Manhole)	- · · -E- · · -	Existing Power Line
	Proposed Utility Access (Manhole)	· · · · E2· · · ·	Existing Power Line (Second Company)
<b>\overline</b>	Fire Hydrant	TV	Cable Television Line
<b>●</b> WH	Water Hydrant (Rural)		


• • •	Guardrail (Beam or Cable)					
<b>■</b> GP	Guard Post (one or two)					
	Guard Post (over two)					
⊙ FP	Filler Pipe					
⊙ GV	Gas Valve					
O WV	Water Valve					
⊙ SL	Speed Limit Sign					
⊙ MM	Mile Marker Post					
SIGN	Sign					
⊙ WHU	Water Hook Up					
□ RT	Radio Tower					
⊙ ТА	Tower Anchor					
□ ЕВ	Electric Box					
□ ТСВ	Traffic Signal Control Box					
☐ RRB	Rail Road Signal Control Box					


☐ TSB Telephone Switch Box



#### LITHLITIES CONTACTS

	UTILITIES CONT.	ACIS	
COMPANY	ADDRESS	REPRESENTATIVE	TELEPHONE
City of Adel	P.O. Box 248 Adel, Iowa 50003	Jordon Altenhofen	(515) 993-4525
CenturyLink		Tom Sturmer	(720) 578-8090
Dallas County	801 Court St. Adel, Iowa 50003	Cliff Gibson or Todd Noah	(515) 993-5818
MidAmerican Energy (Electric and Gas)	P.O. Box 657 Des Moines, Iowa 50306	Craig Ranfeld	(515) 252-6632
Mediacom		Paul May	(515) 246-2252







DALLAS COUNTY
PARKING LOT REHABILITATION - PHASE 1
ADEL, IOWA
LEGEND AND SYMBOLS

PROJECT NO 60579114
FILENAME

SHEET NO DRAWING NO

2

			Contract	As-Built
<u>Item No.</u>	<u>Description</u>	<u>Unit</u>	<u>Quantity</u>	<b>Quantity</b>
1	CLASS 10 EXCAVATION	CY	192.0	
2	REMOVAL OF CURB AND GUTTER	LF	104.0	
3	REMOVAL OF SIDEWALK & DRIVEWAY	SY	155.0	
4	REMOVAL OF PAVEMENT	SY	275.0	
5	MODIFIED SUBBASE, 6-INCH	SY	285.0	
6	PAVEMENT, STANDARD OR SLIP-FORM, PCC, 7-INCH, TYPE C	SY	205.0	
7	HOT MIX ASPHALT, COMMERCIAL MIX (INCLUDES ASPHALT BINDER)	TON	190.0	
8	SIDEWALK, PCC, 4 INCH, TYPE C	SY	103.0	
9	DRIVEWAY, PCC, 7 INCH, TYPE C	SY	64.0	
10	TRAFFIC CONTROL	LS	1.0	
11	PAINTED PAVEMENT MARKINGS, WATERBORNE	STA	9.5	
12	PAINTED SYMBOLS AND LEGENDS	EA	1.0	
13	CONSTRUCTION SURVEY	LS	1.0	
14	SODDING	SQ	5.0	
15	PERIMETER AND SLOPE SEDIMENT CONTROL DEVICE, 9 IN.	LF	350.0	
16	REMOVAL OF PERIMETER AND SLOPE SEDIMENT DEVICE	LF	350.0	
17	CONCRETE WASHOUT	LS	1.0	

### **ESTIMATE REFERENCE INFORMATION**

- 1. EXCAVATE PER SUDAS SECTION 2010. ALL EXCESS MATERIAL SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE PROPERLY DISPOSED OF OFFSITE.
- 2. REMOVE PER SUDAS SECTION 7040.
- 3. REMOVE PER SUDAS SECTION 7030. INCLUDES DRIVEWAY REMOVAL. REMOVE TO EXISTING JOINTS. CONTRACTOR TO USE CAUTION WHEN WORKING NEXT TO RAPIDS STREET. DAMAGE TO BRICKS SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE.
- 4. REMOVE PER SUDAS SECTION 7040.3.08. INCLUDES BOTH PCC AND HMA PAVEMENT REMOVAL.
- 5. MEET THE REQUIREMENTS OF SUDAS SECTION 2010. 6-INCH SUBGRADE PREPARATION SHALL BE INCIDENTAL TO THIS ITEM.
- 6. MEET REQUIREMENTS OF SUDAS SECTION 7010. CLASS 3 AGGREGATE DURABILITY. CURB AND GUTTER INTEGRAL TO PARKING AREAS SHALL BE INCIDENTAL TO THIS ITEM.
- 7. MEET REQUIREMENTS OF SUDAS SECTION 7021. INSTALL LEVELING BASE COURSE PRIOR TO FINAL 2" SURFACE COURSE. LEVELING COURSE IS INCLUDED IN THIS ITEM.
- 8. MEET REQUIREMENTS OF SUDAS SECTION 7030. CLASS 2 AGGREGATE DURABILITY. CLASS A SIDEWALK SHALL USE JOINT DETAIL 2 ON SUDAS DETAIL 7030.202.
- 9. MEET REQUIREMENTS OF SUDAS SECTION 7030. CLASS 3 AGGREGATE DURABILITY.
- 10. MEET REQUIREMENTS OF SUDAS SECTION 8030. REMOVAL, STOCKPILING, AND RE-INSTALLATION OF EXISTING TRAFFIC SIGNS SHALL BE INCIDENTAL TO THIS ITEM.
- 11. MEET THE REQUIREMENTS OF SUDAS SECTION 8020.
- 12. MEET THE REQUIREMENTS OF SUDAS SECTION 8020.
- 13. MEET REQUIREMENTS OF SUDAS SECTION 110130.
- 14. MEET REQUIREMENTS OF SUDAS SECTION 9020.
- 15. MEET REQUIREMENTS OF SUDAS SECTION 9040. PLACE AT DIRECTION OF ENGINEER.
- 16. MEET REQUIREMENTS OF SUDAS SECTION 11050.

DRN					
DES					
CHK					
APP					
Copyright ©	_				
AECOM All Rights Reserved	9	REVISIONS	DRN CHK	¥	DATE



PARKING LOT REHABILIATION - PHASE 1
ADEL, IOWA
QUANTITIES AND ESTIMATE
REFERENCE NOTES

AUGUST, 2018
PROJECT NO 60579114
FILENAME

SHEET NO DRAWING NO

3

Contractor shall check for locations of utilities, drainage structures or other facilities in the construction area. Any damage to such facilities due to the contractor's carelessness shall be corrected at the contractor's expense.

01-20-84

All holes resulting from operations of the contractor, including removal of guardrail posts, fence posts, utility poles, or foundation studies, shall be filled and consolidated to finished grade as directed by the engineer to prevent future settlement. The voids shall be filled as soon as practical - preferably the day created and not later than the following day. Any portion of the right-of-way or project limits (including borrow areas and operation sites) disturbed by any such operations shall be restored to an acceptable condition. This operation shall be considered incidental to other bid items in project.

10-29-02

It shall be the contractor's responsibility to provide waste areas or disposal sites for excess material (excavated material or broken concrete) which is not desirable to be incorporated into the work involved on this project. These areas shall not impact wetlands or "Waters Of The U.S." No payment for overhaul will be allowed for material hauled to these sites. No material shall be placed within the right-of-way, unless specifically stated in the plans.

10-27-98

The contractor shall apply necessary moisture to the construction area and haul roads to prevent the spread of dust. Refer to Article The cost of dust control shall be incidental to the project.

01-20-84

In order to avoid any unnecessary surface breaks or premature spalling, the contractor is cautioned to exercise extreme care when performing any of the necessary saw cutting operations for the proposed pavement removal.

01-20-84

The contractor shall not disturb desirable grass areas and desirable trees outside the construction limits. The contractor will not be permitted to park or service vehicles and equipment or use these areas for storage of materials. Storage, parking and service area(s) will be subject to the approval of the resident engineer.

09-27-94

The top 6 inches of the disturbed areas shall be free of rock and debris and shall be suitable for the establishment of vegetation, subject to the approval of the Engineer.

10-28-97

The contractor is expected to have materials, equipment, and labor available on a daily basis to install and maintain erosion control features on the project. This may involve seeding, silt fence, rock ditch checks, silt basins, or silt dikes.

10-29-02

BEFORE YOU DIG: IOWA ONE CALL# 1-800-292-8989

01-93

All traffic control devices utilized shall be in accordance with the Manual on Uniform Traffic Control Devices and Section 8030 of the SUDAS Specifications.

01-93

All traffic control devices shall be furnished, erected, maintained and removed by the contractor.

ET-E.37

ET-F.1

ET-F.6

ET-F.7

ET-G.7

01-9

204-2

213-1

213-4

232-5

232-8

232-10

262-3

ET-E.34

Where public utility fixtures are shown as existing on the plans or encountered within the construction area, it shall be the responsibility of the Contractor to notify the owners of those utilities prior to the beginning of any construction. The Contractor shall afford access to these facilities for necessary modification of services. Underground facilities, structures and utilities have been plotted from available surveys and records, and therefore their locations must be considered approximate only. It is possible there may be others, the existence of which is presently not known or shown. It is the Contractor's responsibility to determine their existence and exact location and to avoid damage thereto. No claims for additional compensation will be allowed to the Contractor for any interference or delay caused by such work.

01-93

Contractors shall arrange with the various utility companies for support or relocation of any utilities and/or utility poles. Any charge for temporary supporting or relocating any utilities and/or utility poles shall be paid by the Contractor.

01-93

The information concerning underground utilities was compiled from information and sketches furnished by or obtained from utility companies and City records. The owner and the Engineer do not guarantee their accuracy. The Contractor is advised to determine the exact locations from the available sources of information or provide his own means of detection. The only case in which the Engineer will consider redesign or relocation of a proposed facility in the project is when an existing utility is located within the limit of two vertical lines located on the exterior of the proposed pipe or facility. In this case, the Engineer will try to have the utility relocated. If such a relocation is impossible, he will consider redesign or relocation of the proposed facilities. In both cases, Contractor shall be responsible for all underground utilities and shall not be separately compensated for delays or extra cost.

01-93

Prior to opening an excavation, effort shall be made to determine whether underground installations; i.e., sewer, water, fuel, electric lines, etc., will be encountered, and if so, where such underground installations are located. When the excavation approaches the approximate locations of such an installation, the exact locations shall be determined by careful probing or hand digging, and when it is uncovered, adequate protection shall be provided for the existing installation. All known owners of underground facilities in the area concerned shall be advised of proposed work at least 48 hours prior to the start of actual excavation.

01-93

The Contractor shall prepare a detailed schedule of work which shall be submitted at the preconstruction conference. The schedule shall show anticipated equipment and material deliveries and completion of major tasks in the project.

01-93

The general Contractor shall be responsible for the coordination of work between all equipment suppliers, crafts and subcontractors involved in the project including staging of construction and construction details.

R-12

All trenches for storm sewer and for removal of existing storm sewer pipe and excavated areas adjacent to intakes and storm sewer manholes shall be backfilled and compacted to 98 percent of standard proctor density according to descriptions included in the special provisions for sanitary sewers. Compaction of backfill will not be measured or paid for separately but will be considered as incidental to the prices bid for the various sizes of storm sewer pipe, intakes, manholes and pipe removal.

R-18

Contractor shall protect all utilities. Contractor shall protect all storm sewer inlets from siltation and debris during

Finishing of border areas beyond curbs shall be considered incidental to other work.

Unless otherwise directed or authorized, all asphaltic cement concrete and other bituminous materials which are not specifically addressed or described in the plans shall become the property of the contractor.

Any saw cutting noted on the plans shall be construed to be incidental to other contract items.

The location for storage of equipment by the contractor during nonworking hours shall be as approved by the City of Adel and Dallas County.

Project shall be constructed according to 2018 version of SUDAS Specifications unless otherwise noted.

AECOM

DALLAS COUNTY PARKING LOT REHABILITATION - PHASE 1 ADEL, IOWA


NOTES


AUGUST, 2018
PROJECT NO 60579114


FILENAME SHEET NO


DRAWING NO


STAGE 1- ADDITIONAL STREET PARKING  1. SHIFT TRAFFIC ON IN 1011 STREET TO THE WEST UTILIZING CURRENT PARKING LANE. CHANNELIZERS SHALL BE UTILIZED TO ALLOW FOR TWO-WAY TRAFFIC ADJACENT TO PROPOSED STREET PARKING.  2. COMPLETE REMOVALS IN NEW STREET PARKING AND SIDEWALK AREA AND PREPARE SITE FOR CONSTRUCTION.  3. EXCAVATE AND INSTALL MODIFIED SUBBASE AND NEW PARKING AND SIDEWALK PAVEMENT AS SHOWN IN THE PLANS.  4. TOPSOIL AND SOD THE AREAS AT THE NORTH AND SOUTH END OF THE PARKING AREA AS SHOWN ON THE PLANS.  5. STAGE 1 MAY BE CONSTRUCTED CONCURRENTLY WITH STAGE 2.  STAGE 2. DAM PARKING LOT  1. CLOSE ORNEWAYS FROM COURT STREET, N. 10TH STREET AND THE ALLEY TO THE DEPARTMENT OF MOTOR VEHICLES PARKING LOT.  2. CLOSE SIDEWALK ON NORTH SIDE OF STREETS.  3. COMPLETE REMOVALS IN SIDEWAYS AND PARKING LOT AND PREPARE FOR CONSTRUCTION.  4. INSTALL NEW SIDEWALK, DRIVEWAYS AND HIM OVERLAY.  5. TOPSOIL AND SOD DISTURBED BARKS.  6. STAGE 2 CANNOT BEGIN UNTIL AFTER ADM SCHOOL BEGINS ON AUGUST 23, 2018.  7. STAGE 2 MAY BE CONSTRUCTED CONCURRENTLY WITH STAGE 1.		
	DALLAS COUNTY  ON 133FO A  ON	STAGING NOTES GOST, 2018





























113-10 4-18-2017

### SIDEWALK COMPLIANCE

See S Sheets

* Does not include curb
Staking required by Contracting Authority per Article 2511.03 of the Standard Specifications.

Point 1	t- D-i-t	cide all Designation	_" PCC Sidewalk	Distance*	Δ Elevation	Slope	Acceptable	Staking Required on	Measured	T-1+1-1-	Initials Remarks	VALUES	FOR INFORMA S USED TO DE SLO	TERMINE	
oint	to Point	Sidewalk Designation	Sidewalk				Constructed Range	this Quadrant?	Slope	Initials	Remarks	Point	Station	0ffset	Elevation
				FT	FT	%	Pos. or Neg.		%	1					
01	102	Sidewalk Running Slope	4	4.08	-0.02	-0.5%	0.5% to 5.0%					101	11+56.37	44.26	890.78
.01	102	Match Existing Cross Slope	4	4.54	-0.01	-0.2%	Match Existing					102	11+50.37	44.25	890.76
.02	103	Landing/Turning Space	4	1.00	0.01	1.0%	0.1% to 2.0%					103	11+51.30	44.25	890.77
.02	108	Landing/Turning Space	4	5.00	0.07	1.4%	0.1% to 2.0%					104	11+47.30	44.25	890.83
.03	104	Landing/Turning Space	4	4.00	0.06	1.5%	0.1% to 2.0%					105	11+47.25	49.25	890.91
.04	105	Landing/Turning Space	4	5.00	0.08	1.6%	0.1% to 2.0%	Yes	Yes			106	11+47.19	55.34	890.92
.05	106	Sidewalk Running Slope	4	6.09	0.01	0.2%	0.5% to 5.0%					107	11+51.26	55.40	890.97
05	108	Landing/Turning Space	4	5.00	-0.08	-1.6%	0.1% to 2.0%	Yes	Yes			108	11+52.25	49.25	890.83
.06	107	Match Existing Cross Slope	4	4.07	0.05	1.2%	Match Existing					109	11+56.43	48.80	890.77
L07	108	Sidewalk Running Slope	4	6.03	-0.14	-2.3%	0.5% to 5.0%					110	11+39.44	49.23	891.08
.08	109	Sidewalk Running Slope	4	4.20	-0.06	-1.4%	0.5% to 5.0%					111	11+39.44	44.23	891.16
110	111	Sidewalk Cross Slope	4	5.00	0.08	1.5%	0.5% to 2.0%								
.10	105	Sidewalk Running Slope	4	7.81	-0.17	-2.2%	0.5% to 5.0%								
11	104	Sidewalk Running Slope	4	7.81	-0.33	-4.2%	0.5% to 5.0%	Yes	Yes						
01	202	Landing/Tunning Coase	4	4 22	0.06	1 49/	0 1% to 2 0%					201	11,51 (0	12 20	900 00
201	204	Landing/Turning Space	4	4.22 5.00	0.06	1.4%	0.1% to 2.0% 0.1% to 2.0%					201	11+51.60	13.38	890.08
201	203	Landing/Turning Space Landing/Turning Space	4	6.34	0.07	1.4%	0.1% to 2.0%					202	11+47.60 11+47.55	13.34 18.34	890.14 890.21
203	204	Landing/Turning Space	4	4.00	-0.06	-1.5%	0.1% to 2.0%					204	11+51.55	18.38	890.15
205	206	Landing/Turning Space	4	4.00	0.06	1.5%	0.1% to 2.0%					205	11+51.90	18.37	890.15
205	208	Landing/Turning Space	4	5.00	-0.07	-1.4%	0.1% to 2.0%					206	11+47.90	18.41	890.21
206	207	Landing/Turning Space	4	6.41	-0.07	-1.1%	0.1% to 2.0%					207	11+47.86	13.41	890.14
97	208	Landing/Turning Space	4	4.24	-0.06	-1.4%	0.1% to 2.0%					208	11+51.86	13.37	890.08
209	205	Sidewalk Running Slope	4	20.61	-0.59	-2.9%	0.5% to 5.0%					209	11+52.10	38.97	890.74
209	210	Sidewalk Cross Slope	4	4.00	0.06	1.5%	0.5% to 2.0%					210	11+48.10	39.01	890.80
210	206	Sidewalk Running Slope	4	20.61	-0.59	-2.9%	0.5% to 5.0%								
201	202	Matab Friedrica Casas Class	1	2.07	0.11	2 09/	Matal Fairting					201	11.52.50	00.72	000 11
301 301	302 304	Match Existing Cross Slope Landing/Turning Space	4	3.97 5.00	0.11	2.8%	Match Existing 0.1% to 2.0%	Yes	Yes			301 302	11+52.59 11+48.59	88.73 88.90	890.11 890.22
302	303	Landing/Turning Space	4	5.13	0.03	0.6%	0.1% to 2.0%	res	res			303	11+48.59	83.77	890.25
303	304	Landing/Turning Space	4	4.00	-0.06	-1.5%	0.1% to 2.0%					304	11+52.54	83.73	890.19
		<i>J.</i>													
101	402	Landing/Turning Space	4	4.99	0.03	0.7%	0.1% to 2.0%					401	10+87.96	30.50	891.23
101	412	Landing/Turning Space	4	7.61	0.10	1.4%	0.1% to 2.0%					402	10+82.96	30.50	891.26
102	403	Landing/Turning Space	4	3.37	0.03	0.9%	0.1% to 2.0%					403	10+79.59	30.50	891.29
102	413	Landing/Turning Space	4	7.62	0.14	1.8%	0.1% to 2.0%	Yes	Yes			404	10+74.58	30.50	891.33
103	404	Landing/Turning Space	4	5.01	0.04	0.8%	0.1% to 2.0%					405	10+74.59	38.13	891.41
103	414	Landing/Turning Space	4	7.62	0.09	1.2%	0.1% to 2.0%					406	10+74.60	44.13	891.47
104	405	Landing/Turning Space	4	7.63	0.08	1.0%	0.1% to 2.0%					407	10+74.59	49.13	891.39
105	406	Sidewalk Running Slope	4	6.01	0.06	0.9%	0.5% to 5.0%					408	10+79.59	49.14	891.37
105 106	414 407	Landing/Turning Space Landing/Turning Space	4	5.00 5.00	-0.03 -0.08	-0.6% -1.5%	0.1% to 2.0% 0.1% to 2.0%					409 410	10+82.96 10+87.96	49.14 49.15	891.36 891.33
106	415	Landing/Turning Space	4	5.00	-0.02	-0.4%	0.1% to 2.0%					411	10+87.96	44.15	891.41
107	408	Landing/Turning Space	4	5.00	-0.02	-0.4%	0.1% to 2.0%					412	10+87.96	38.11	891.33
108	409	Sidewalk Running Slope	4	3.37	-0.01	-0.3%	0.5% to 5.0%					413	10+82.96	38.12	891.40
108	415	Landing/Turning Space	4	5.00	0.08	1.5%	0.1% to 2.0%					414	10+79.59	38.15	891.38
.09	410	Landing/Turning Space	4	5.00	-0.03	-0.6%	0.1% to 2.0%					415	10+79.60	44.14	891.49
-09	416	Landing/Turning Space	4	5.00	0.08	1.5%	0.1% to 2.0%					416	10+82.97	44.14	891.44
10	411	Landing/Turning Space	4	5.00	0.08	1.5%	0.1% to 2.0%					417	10+48.90	44.09	891.59
11	412	Sidewalk Running Slope	4	6.04	-0.08	-1.2%	0.5% to 5.0%					418	10+48.89	49.09	891.51
11	416	Landing/Turning Space	4	5.00	0.03	0.6%	0.1% to 2.0%					419	10+12.36	44.03	891.29
12	413	Landing/Turning Space	4	5.00	0.07	1.4%	0.1% to 2.0%					420	10+12.32	49.03	891.26
13	414	Landing/Turning Space	4	3.37	-0.02	-0.6%	0.1% to 2.0%								
13	416	Sidewalk Running Slope	4	6.03	0.04	0.6%	0.5% to 5.0%								
14	415	Sidewalk Running Slope	4	6.02	0.07	1.1%	0.5% to 5.0%								
<b>11</b> 5	416	Sidewalk Running Slope	4	3.37	-0.01	-0.3%	0.5% to 5.0%								
117	418	Sidewalk Running Slope	4	5.00	-0.08	-1.5%	0.5% to 5.0%  Match Existing								
119	420	Match Existing Cross Slope	4	5.01	-0.03	-0.6%									



DALLAS COUNTY PARKING LOT REHABILITATION - PHASE 1 ADEL, IOWA	SIDEWALK
DATE	
AUC PROJECT NO	SUST, 2018
FILENAME	60579114

DRAWING NO

NIC

### SIDEWALK COMPLIANCE

See S Sheets

* Does not include curb Staking required by Contracting Authority per Article 2511.03 of the Standard Specifications.

91 91 92 92	502 506	Sidewalk Designation	Sidewalk	Distance*		Slope	Acceptable	Required on	Measured	1		1	SLO	DES	
91 92 92 93	506				Δ Elevation	Бторс	Constructed Range	this Quadrant?	Slope	Initials	Remarks	Point	Station	Offset	Elevati
91 92 92 93	506			FT	FT	%	Pos. or Neg.		%						
91 92 92 93	506	Ramp Running Slope	6	9.00	0.50	5.5%	0.5% to 8.3%					501	11+23.00	35.50	890.7
92		Ramp Cross Slope	6	5.00	-0.09	-1.8%	0.1% to 2.0%	Yes	Yes			502	11+14.00	35.50	891.2
92	503	Landing/Turning Space	4	5.00	0.01	0.2%	0.1% to 2.0%					503	11+09.00	35.50	891.2
93	505	Landing/Turning Space	4	5.00	-0.08	-1.5%	0.1% to 2.0%					504	11+09.00	30.50	891.1
	504	Landing/Turning Space	4	5.00	-0.08	-1.5%	0.1% to 2.0%					505	11+14.00	30.50	891.:
93	507	Sidewalk Running Slope	4	8.17	-0.01	-0.1%	0.5% to 5.0%					506	11+23.00	30.50	890.6
94	505	Landing/Turning Space	4	5.00	-0.01	-0.2%	0.1% to 2.0%					507	11+00.83	35.50	891.
94	520	Sidewalk Running Slope	4	8.17	-0.01	-0.1%	0.5% to 5.0%					508	10+95.83	35.50	891.2
95	506	Ramp Running Slope	6	9.00	-0.51	-5.7%	0.5% to 8.3%					509	10+86.83	35.50	890.8
97	508	Landing/Turning Space	4	5.00	0.01	0.2%	0.1% to 2.0%					510	10+86.86	39.06	890.8
97	520	Landing/Turning Space	4	5.00	-0.08	-1.5%	0.1% to 2.0%					511	10+80.17	39.06	890.8
98	509	Ramp Running Slope	6	9.00	-0.43	-4.8%	0.5% to 8.3%					512	10+80.17	35.50	890.8
98	519	Landing/Turning Space	4	5.00	-0.08	-1.5%	0.1% to 2.0%					513	10+71.17	35.50	891.4
	510	Landing/Turning Space	4	3.56	0.04	1.1%	0.1% to 2.0%					514	10+66.17	35.50	891.4
99	512	Landing/Turning Space	4	6.66	0.02	0.3%	0.1% to 2.0%					515	10+66.17	30.50	891.4
	518	Landing/Turning Space	4	5.00	-0.09	-1.8%	0.1% to 2.0%	Yes	Yes			516	10+71.17	30.50	891.
	511	Landing/Turning Space	4	6.66	0.02	0.3%	0.1% to 2.0%					517	10+80.17	30.50	890.
11	512	Landing/Turning Space	4	3.57	-0.04	-1.1%	0.1% to 2.0%					518	10+86.83	30.50	890.
	513	Ramp Running Slope	6	9.00	0.61	6.7%	0.5% to 8.3%					519	10+95.83	30.50	891.3
12	517	Landing/Turning Space	4	5.00	-0.09	-1.8%	0.1% to 2.0%	Yes	Yes			520	11+00.83	30.50	891.:
	514	Landing/Turning Space	4	5.00	0.04	0.8%	0.1% to 2.0%					521	10+26.98	35.50	891.
13	516	Landing/Turning Space	4	5.00	-0.08	-1.5%	0.1% to 2.0%					522	10+21.98	35.50	891.
L4	515	Landing/Turning Space	4	5.00	-0.08	-1.5%	0.1% to 2.0%					523	10+12.98	35.50	891.
L4	521	Sidewalk Running Slope	4	39.19	0.29	0.7%	0.5% to 5.0%					524	10+12.94	30.50	891.3
L5	516	Landing/Turning Space	4	5.00	-0.04	-0.8%	0.1% to 2.0%					525	10+21.98	30.50	891.7
15	526	Sidewalk Running Slope	4	39.19	0.29	0.7%	0.5% to 5.0%					526	10+26.98	30.50	891.7
16	517	Ramp Running Slope	6	9.00	-0.62	-6.9%	0.5% to 8.3%					320	20.20.20	50150	
17	518	Landing/Turning Space	4	6.66	-0.02	-0.3%	0.1% to 2.0%								
18	519	Ramp Running Slope	6	9.00	0.45	5.0%	0.5% to 8.3%								
19	520	Landing/Turning Space	4	5.00	-0.01	-0.2%	0.1% to 2.0%								
21	522	Landing/Turning Space	4	5.00	0.04	0.8%	0.1% to 2.0%								
21	526	Landing/Turning Space	4	5.00	-0.08	-1.5%	0.1% to 2.0%								
22	523	Ramp Running Slope	6	9.00	-0.47	-5.2%	0.5% to 8.3%								
22	525	Landing/Turning Space	4	5.00	-0.08	-1.5%	0.1% to 2.0%								
23	524	Match Existing Cross Slope	4	5.00	-0.04	-0.8%	Match Existing								
24	525	Ramp Running Slope	6	9.04	0.43	4.8%	0.5% to 8.3%								
25	526	Landing/Turning Space	4	5.00	-0.04	-0.8%	0.1% to 2.0%								
							2727 22 2120						·		
91	604	Match Existing Cross Slope	4	4.37	0.01	0.2%	Match Existing					601	21+68.90	78.94	891.
91	602	Sidewalk Running Slope	4	25.51	0.11	0.4%	0.5% to 5.0%			1		602	21+43.39	78.88	891.4
92	603	Sidewalk Cross Slope	4	4.50	-0.07	-1.5%	0.5% to 2.0%					603	21+43.40	83.38	891.4
93	604	Sidewalk Running Slope	4	25.56	-0.03	-0.1%	0.5% to 5.0%			1		604	21+68.96	83.31	891.
95	608	Sidewalk Cross Slope	4	4.50	-0.07	-1.5%	0.5% to 2.0%					605	21+22.67	78.93	891.5
95	606	Sidewalk Running Slope	4	12.87	-0.03	-0.2%	0.5% to 5.0%			1		606	21+09.81	79.09	891.5
96	607	Match Existing Cross Slope	4	4.38	-0.14	-3.2%	Match Existing			1		607	21+09.76	83.46	891.
97	608	Sidewalk Running Slope	4	12.93	0.10	0.8%	0.5% to 5.0%					608	21+22.68	83.43	891.4
								1			•				
91	704	Match Existing Cross Slope	4	3.87	-0.19	-4.9%	Match Existing					701	20+33.03	23.53	891.
	703	Match Existing Cross Slope	4	3.81	-0.13	-3.4%	Match Existing			1		702	20+32.76	24.34	891.4
$\neg$		3										703	20+28.95	24.37	891.
$\overline{}$												704	20+29.16	23.57	891.

Ž
8
<b>M</b>

SIDEWALK DATE AUGUST, 2018
PROJECT NO 60579114

FILENAME

DRAWING NO 18

NIC

